

INVITATION TO BID

Notice is hereby given that the City of Happy Valley will open sealed bids from qualified contractors for the

2020 STREET IMPROVEMENT PROJECT

ODOT CLASS OF WORK: Asphalt Concrete Paving and Oiling, and Pavement Markings

PUBLIC BID OPENING.....Thursday, June 11, 2020 at 2:00 PM

FIRST-TIER SUBCONTRACTOR DISCLOSURE FORM DUE.....Thursday, June 11,, 2020 at 4:00 PM

No bids will be received or considered if submitted electronically or after the time of closing.

This project generally includes reconstruction, repair, and overlay street improvement for eight (8) streets: Proposed work includes the following:

Schedule 'A' (SE 129th Avenue) includes the following proposed work:

- **Pavement Grinding to Full-Depth (4"+/-): 724 +/- square yards,**
- **Cement-Treated Sub-Grade (CTB): 724 +/- square yards (22 tons PCC, 6% Application Rate),**
- **Paving Street to 4" Thickness: 724 +/- square yards (160 tons), and**
- **Striping: 16+/- square feet of 12" stop bar**

Schedule 'B' (SE Purple Finch Loop) includes the following proposed work:

- **Pavement Grinding up to 2" Depth: 1,300+/- square yards,**
- **Overlay Street to 2" Thickness: 2,740+/- square yards (303 tons),**
- **Striping: 24+/- square feet of 12" stop bars,**
- **ADA Ramp Construction: Removal and construction of (4) four ramps**

Schedule 'C' (SE Solomon Court) includes the following proposed work:

- **Pavement Grinding to Full-Depth (4"+/-): 3,053+/- square yards,**
- **Paving Street to 4" Thickness: 3,053+/- square yards (672 tons),**
- **Cement-Treated Sub-Grade (CTB): 3,053+/- square yards (93 tons PCC, 6% application Rate)**
- **Striping: 12+/- square feet of 12" stop bar,**
- **ADA Ramp Construction: Removal and construction of (7) seven ramps**
- **Commercial Driveway Construction: Removal and construction of (1) driveway**

Schedule 'D' (SE Cresthill Road) includes the following proposed work:

- **Pavement Grinding to Full-Depth (4"+/-): 1,094+/- square yards,**
- **Cement-Treated Sub-Grade (CTB): 1,094+/- square yards (34 tons, 6% Application Rate),**
- **Paving Street to 4" Thickness: 1,094+/- square yards (240 tons),**
- **Striping: 16+/- square feet of 12" bars,**

- **ADA Ramp Construction:** Removal and construction of (2) two ramps
- **Commercial Driveway Construction:** Removal and construction of (1) driveway

Schedule 'E' (SE 155th Avenue) includes the following proposed work:

- **Pavement Grinding to Full-Depth (4" +/-):** 2,368 +/- square yards,
- **Paving Street to 4" Thickness:** 2,368 +/- square yards (**515** tons),
- **ADA Ramp Construction:** Removal and construction of (2) two ramps
- **Concrete Stair Construction:** Removal and construction of (1) one stair
- **Striping:** 16 +/- square feet of 12" stop bar

Schedule 'F' (SE 156th Avenue) includes the following proposed work:

- **Pavement Grinding up to 2" Depth:** 2,104 +/- square yards,
- **Overlay Street to 2" Thickness:** 2,104 +/- square yards (**231** tons),
- **Pavement Fabric:** 18,936 +/- square feet.

Schedule 'G' (SE Vivian Way) includes the following proposed work:

- **Pavement Grinding up to 2" Depth:** 350 +/- square yards,
- **Overlay Street to 2" Thickness:** 350 +/- square yards (**39** tons),
- **Pavement Fabric:** 3,150 +/- square feet.

Schedule 'H' (SE Nyla Way) includes the following proposed work:

- **Pavement Grinding up to 2" Depth:** 603 +/- square yards,
- **Overlay Street to 2" Thickness:** 603 +/- square yards (**67** tons),
- **Striping:** 12 +/- square feet of 12" bars,
- **Pavement Fabric:** 5,427 +/- square feet,
- **ADA Ramp Construction:** Removal and construction of (2) two ramps

Construction must be completed no later than the **Friday, August 28, 2020**. Once construction on the project has begun, the contractor must reach substantial completion within **60** days of commencing activity.

COVID-19 Physical Distancing Plan

Bidder must submit a work plan or written description explaining how the bidder will meet all Center for Disease Control (CDC) and Oregon Health Authority (OHA) recommendations on physical distancing and personal protective equipment to slow the spread of COVID-19. The City may request updated plans as recommendations change and actions should reflect current recommendations at the time of construction. This plan may be a word document or work plan outline how physical distancing will be met while performing work as described in the scope of work.

The City has the ability to adjust the project schedule due to state mandates.

Project and bid documents are available on the City's website <https://www.happyvalleyor.gov/>

To perform work, bidders must be prequalified with the Oregon Department of Transportation for the class of work defined above. Proof of prequalification must be submitted to the City by **4:00 PM** on the **Date of Public Bid Opening**.

Sealed bids are to be sent to **Carol Earle, P.E.**, City Engineer as shown on the schedule of bid, and may not be submitted by electronic means. All bids received by the date and time of Public Bid Opening will be opened at the City Hall address at the designated date and time noted above.

This public works contract is subject to State of Oregon prevailing rates of wage requirements, per **ORS 279C.800** through **279C.870**. The City will not receive or consider bids unless the bid contains a statement by the bidder that the bidder will comply with **ORS 279C.830**.

Bidders must be qualified in accordance with the applicable parts of **ORS279C** in order to enter into a contract with the City. No bid shall be considered unless the bidder is registered with the Oregon Construction Contractors. Bidder shall also identify whether bidder is a current resident, as defined in **ORS 279A.120**.

The City of Happy Valley may reject any and all bids that do not comply with prescribed public bidding and contracting procedures and requirements, including the requirement to demonstrate the bidder's responsibility under **ORC 279C.375(3)(b)**, Award and Execution of Contract, and that the City of Happy Valley may reject for good cause any and all bids after finding that doing so is in the public interest.

CITY OF HAPPY VALLEY

Economic & Community Development Department

Engineering Division

Carol Earle, P.E.
City Engineer

NOTICE IS DATED the **21st of May, 2020**, and published as of this date on:

- Daily Journal of Commerce, Oregon website <https://djcoregon.com/>
- City of Happy Valley website <https://www.happyvalleyor.gov/>