

Mayor
Honorable Tom Ellis



City Manager
Jason A. Tuck, ICMA-CM

Addendum No. 1

May 30, 2023

For The Contract Documents for The

2023 Street Improvement Project (CIP-02-23)

NOTICE TO ALL PLAN HOLDERS:

You are hereby notified of the following clarifications, additions, and/or revisions to the contract documents for the above referenced project:

Question from Contractor: *"I think best option would be to excavate, install base rock & Pave Base Lift on the NE & NW driveways before you Cement Treat other section. The problem is there is no bid item for that work. Also, will we be able to do 2" grind section at the same time we do the 5" section? It would have car traffic on it while the CTB cured for 7 days?"*

Answer:

The depth of the stamped concrete crosswalks is not known. After the crosswalks are removed additional excavation may be required to provide the appropriate pavement section. If additional rock is necessary, it will be paid for under bid item A.14. The base lift quantity of pavement will be paid for under bid item A.15.

The contractor can perform the 2" grinds and 5" grinds all at the same time if temporary cold mix is placed at the ends to minimize the abrupt edge.

The CTB section will not need to be cured for 7 days. Plan on placing CTB early one day and paving base lift and final lift on the following day.

Contractors Acknowledgement of Addendum No. 1 (CIP-02-23):

Signature

Date

16000 SE Misty Drive, Happy Valley, Oregon 97086-4288
Telephone: (503) 783-3800 Fax: (503) 658-5174
happyvalleyor.gov

Preserving and enhancing the safety, livability and character of our community