



**NOTES:**

1. B&B STOCK MAY BE SUBSTITUTED WITH CONTAINER STOCK OF EQUAL GRADE.
2. CONTAINER STOCK MAY BE SUBSTITUTED WITH B&B STOCK OF EQUAL GRADE.
3. PLANT MATERIAL SHALL CONFORM WITH AMERICAN STANDARD FOR NURSERY STOCK, ANSI Z60.1, 2014 EDITION.
4. ALL TREES SHALL BE BRANCHED.
5. IN THE EVENT OF A DISCREPANCY BETWEEN THE PLANT LISTING AND THE DRAWINGS, THE PLANT LISTING SHALL GOVERN THE PLANT SPECIES AND QUANTITIES REQUIRED.
6. IN THE EVENT OF QUESTION OR LACK OF CLARITY ON DRAWINGS, LANDSCAPE CONTRACTOR IS TO CALL PROJECT MANAGER BEFORE PROCEEDING.
7. LANDSCAPE CONTRACTOR TO VERIFY PLANT MATERIAL SPECIES AND QUANTITIES WITH PROJECT MANAGER PRIOR TO PLANTING.
8. REFER TO PLANS AND CITY OF HAPPY VALLEY DEVELOPMENT STANDARDS FOR LANDSCAPING REQUIREMENTS INCLUDING TREE PLACEMENT, TOPSOIL AND PLANTING SPECIFICATIONS.
9. WATER TREE IN AT PLANTING AND DURING THE MAINTENANCE PERIOD IS REQUIRED.
10. TREE STAKES ARE TO BE REMOVED ONCE THE TREE HAS BEEN STABILIZED AND PRIOR TO FINAL WARRANTY INSPECTION/PROJECT ACCEPTANCE.
11. TREE STAKES ARE REQUIRED TO BE A MINIMUM OF 6-FEET FOR OAK TREES.



**CITY OF HAPPY VALLEY  
ENGINEERING DIVISION**  
16000 SE MISTY DRIVE  
HAPPY VALLEY, OR 97086

**DWG NO: 505**

CITY ENGINEER  
SALLY CURRAN, P.E.

**STREET TREE PLANTING**

DATE: 6/10/2022

REVISED BY: KMA